

## **CASE STUDY** TATA STEEL SCUNTHORPE

**Project:** Demolition Of The Breeze Bunker  
**Client:** Tata Steel  
**Date:** March 2011 - April 2011

Ron Hull Demolition Limited's ongoing partnership with Tata Steel continued at the Scunthorpe site when we were awarded the contract to demolish the 32m high steel portal frame tower unit with bunker and associated 2no feed conveyors.

As the works were carried out within a live area of the Tata Steel Scunthorpe site, RHDL worked closely with the client to minimise the potential for third party interface and to ensure that all precautionary measures were established well in advance of commencement with particular attention being the diversion of the access road around the site.

Environmental monitoring was carried out by the client during the works duration and RHDL used the latest dust suppression techniques to minimise any dust impact.

A safe system of work was established through the risk assessment process and it was decided that the 2no feed conveyors would be dismantled and craned down to ground floor level utilising a 220 tonne mobile crane. Once at ground floor level the feed conveyors were processed into suitable lengths for disposal into the onsite BOS plant.

